

# Update on Testing Activities at NREL DER Test Facility


**Ben Kroposki, NREL**

**Distributed Power Integration Engineering and Testing Lead**

**Distributed Power Program  
Review Meeting**


**July 9-10, 2002**

**Madison, WI**




**NREL DER Test Facility – Boulder, CO**

# DER Interconnection System



## Capstone 330 – 30kW Microturbine





# NREL Test Facility

## Interconnection and Systems Integration Testing



**200kW Grid Simulator** – Simulate utility grid and full control of voltage and frequency to test DG response to grid disturbances



**Yokogawa PZ4000** -  
Power analyzer – For  
Data Acquisition and  
measurement

**Load Banks**



**Capstone 330** –  
30kW Microturbine  
running on Propane



**PCC**

# IEEE P1547 Requirements

## Over and Under Frequency


Must disconnect within 0.16s for frequency over 60.5 or under 59.3 Hz.

## Over and Under Voltage

Voltage Range (% of base voltage)	Clearing Time (s)*
$V < 50$	0.16
$50 \leq V < 88$	2
$110 < V < 120$	1
$V \geq 120$	0.16

## Anti-islanding

DR must disconnect within 2 sec. After formation of island.



# Under Frequency Test Results


## Test: Under Frequency

	Setting	Trip Freq
1	59.3	59.40
2	59.3	59.27
3	59.3	59.40
4	59.3	59.37
5	59.3	59.31
<b>AVG</b>	<b>59.3</b>	<b>59.3</b>


Measurement  
Period

Point of  
Disconnection

Frequency at disconnect  
= 59.312 Hz



# Over Frequency Test Results



## Test: Over Frequency


	Setting	Trip Freq
1	60.5	60.55
2	60.5	60.42
3	60.5	60.49
4	60.5	60.49
5	60.5	60.53
AVG	60.5	60.5

Measurement  
Period

Point of  
Disconnection


Frequency at disconnect  
= 60.42Hz





2002/05/24 07:20:02

# Over Voltage Test Results



Step to 120% OV

Start of over voltage condition


Point of Disconnection

Time to disconnect = 33ms

# Anti-Islanding Tests



200kW Grid Simulator



Data Acquisition



Capstone 330



Disconnect time  
= 57ms



## IEEE P1589 – Test Updates

Test procedures are being developed for P1589  
*“Standard Conformance Test Procedures for  
Equipment Interconnecting Distributed Resources  
with Electric Power Systems.”*

Frequency and Voltage Test should be conducted  
in two parts to measure both time and value  
accuracy.

## Future Planned Testing at DERTF

- Finish Capstone testing with updated test procedures
- ASCO SLTS – O/U voltage and frequency, anti-islanding
- Multi-DR Test – Test P1547 requirements with multiple DR (+15) interconnected
- GE Interconnection Device – P1547 tests

**ASCO 7000 SLTS**



**125kW Genset**

