



2004 DOE Hydrogen Fuel Cell And Infrastructure Technologies Program



UTC Power

A United Technologies Company



Atmospheric Fuel Cell Power System for Transportation



Michael Tosca, UTC Power
Matthew Riley, UTC Power

May 25, 2004
Philadelphia



Presentation Agenda

- Objective
- Technical Targets and Barriers
- Background/Approach
- Project Safety
- Program Schedule
- Technical Accomplishments/Progress
- Testing Progress
- Interactions and Collaborations
- Summary
- Future Challenges & Opportunities

Objective

To determine the feasibility of a on-board gasoline reforming 50 kW fuel cell power plant for commercial transportation applications based on the industry and DOE targets for commercialization.

Technical Targets and Barriers

Develop a 45% efficient reformer_based fuel cell power system for transportation operating on clean hydrocarbon or alcohol-based fuel that meets emissions standards, a start_up time of 30 seconds, and a projected manufactured cost of \$45/kW by 2010 and \$30/kW by 2015.*

- Transportation Fuel Processors Technical Barriers (3.4.4.2)*:

I. Start-up/Transient operation

J. Durability

K. Emissions

L. H₂ Purification/CO clean-up

M. Integration/Efficiency

N. Cost

* Excerpts from: "Multi-Year Research, Development and Demonstration Plan, HFCIT, June 3, 2003"

Approach


S400 Gasoline FCPP Phases

- Development in Two Phases (**FY02 - FY04**)
 - Integrated Gasoline Fuel Processor (**FY02 - FY03**)
 - Gasoline in, fuel cell-quality reformat out
 - Development Testing November 2002 – June 2003
 - Data shown here
 - Integrated Fuel Cell Power Plant (**FY03 - FY04**)
 - Assembly completed
 - Started testing in December 2003
 - ANL to conduct verification testing June 2004
 - Available data and projections shown here

Approach

Current S400 Development 2001-2004

System Concept 2001:



Program Steps

2001: Down-select optimum system

2002: Fuel Processor Focus: Start Time, Controllability & Volume

2003: Power Plant Focus: Start Time Controllability, Emissions & Efficiency



FPS



FP1
2002-2003




PPIR
2003-2004

FP1 testing completed
June 6, 2003

System Overview


Simple System Schematic




Project Safety

- Safety reviews of product and test equipment design, and of test processes
 - Codes and Standards, Hazard Analysis, FMEA, FTA, HAZOP
- Standards for Areas with Hazardous Fluids
 - Ventilation and Ventilation Monitoring
 - Gas detection and Fire Suppression
 - Selection of electrical components in potentially hazardous locations
- Out of Limits Conditions
 - Burner and reactor controls
 - Ground fault detection
 - High Temperatures and High Pressures

Project Safety – Safety Analyses



Analysis Risk Ranking



Project Safety – Management of Change

- UTC change process applied to product & test equipment
 - IPD team members review and approve
 - Safety Engineer involvement in IPD
 - Functional checkout of hardware/software changes
- Operating procedures under revision control
- Readiness reviews required for new equipment and chemicals, highlights:
 - Hazards analysis and FMEA
 - Equipment functional checkout
 - Identification of preventative maintenance
 - Procedures and Energy Control
 - PPE assessment, training and communication

Project Safety – Lessons Learned & Other Insights

Two Lessons Learned Examples:

- **Gasoline Heater Control Failure:** Failed solid state relay used for primary control of heater, secondary relays were part of sequential control instead of being continuous. Corrective action: change to continuous and adding further over-temperature redundancy
- **Unintended Flow Path:** Failed active component creates unintended flow path, i.e. blower fails to start, other flows find unintended path. Corrective action: improved flow confirmation and backflow prevention

Other Insights:

- Perform more safety analysis early in project design to identify and resolve safety issues
- Off normal states used for engineering or diagnostic purposes can create challenges. Consideration of all operating states (start-up, shutdown, transitions and off-design) in safety analyses.

Program Schedule – Current Plan

Integrated Fuel Processor Milestones:

Testing Complete
6/6



Integrated Fuel Cell Powerplant Milestones:

7/16
Design Review Complete

11/30
Assembly Complete, Begin Test

5/28
Testing Complete

8/4
Tear Down Inspection & Reporting

9/30
Contact Close



Integrated Fuel Processor



Integrated Fuel Cell Powerplant

Accomplishments/Progress

Series 400 CPO-based FPS

- Benefits
 - No steam generator (smaller)
 - Fuel flexibility (Low sulfur gasoline, naphtha, diesel, F-T diesel, CNG, ethanol...)
 - Reformer durability on CA RFG II / III gasoline (desulfurization by UTC FC)
 - Faster start (lower mass) than ATR
- Start Time: 10 sec CPO ignition, ~5 min FPS
- Volume: 78L Packaged FPS
- Emissions: SULEV
- H₂ Production efficiency:
~75% FPS



Accomplishments/ Progress – iFPS Results

Summary of S400 FP1 Testing Performance Data versus Targets

Data	Target	FP1 Test
• FPS Volume, liters	75	78
• Heat up time, s	165	171
• Number of start/stops	500	111
• Duration of operation (total hrs)	2000	232 hrs
– Longest single run, hrs		10 hrs
• Range of equivalent power, kWe	10-50	10-50
• LHV efficiency, % at rated	≥ 75	69%
• LHV efficiency, % below rated	≥ 70	69-72%


Accomplishments/ Progress – Powerplant Results

Summary of S400 PP1R Testing Performance Data versus Targets

Data	Target	PP1R Test
• PP1R Volume, liters	570	582
• PP1R Mass, kg	455	690
• Start Time (to 10kW Power), min	15	TBD
• Number of start/stops	500	TBD
• Duration of operation (total hrs)	1000	TBD
• Maximum Net Power, kW	25-50	TBD
• System Efficiency at 25% of rated (12.5kW)	≥ 35	TBD
• Ambient Operating Temperature	4 - 40°C	TBD


FP1 Test Results: Start Time

- Start time <5 minutes. Based on stability, H₂ and CO Concentrations




FP1 Test Results: FPS H₂ Production Efficiency

- H₂ Production Efficiency at 10kWe is ~70%




FP1 Test Results: Small Transient Performance

3.5 kW/s small transient. All stable, CO levels as desired



FP1 Test Status: Large Transient Performance

3.5 kW/s large transient. All stable, except CO levels high




FP1 Test Status: SULEV Emissions

- Power plant emissions design goal was to be equal to or less than the 2004 Super Ultra Low Emissions Vehicle (SULEV) standards for vehicles <8500lbs, for CO, NOx and NMHC.
- The SULEV emission limits are specified in terms of g/mile. The emissions for FP1/PP1R were apportioned as total mass amounts for start up, and as concentrations during on-load based on the SULEV limits and the LA4-CH driving mode.
- A methane target of 700 ppm at the powerplant exhaust (3100ppm at FPS exit) and a NMHC target of 1ppm at the FPS exit were additional goals.
- The CSA limit for CO is 20ppm, which is lower than SULEV. The 20ppm target was used herein.

<i>Steady State Goal</i>	<i>Result</i>
NOx \leq 2.1ppm (dry volume)	< 1ppm at all power levels
CO \leq 20ppm (dry volume)	\leq 20ppm at power levels below 30 kW
CH4 \leq 3100ppm (dry volume)	< 3100ppm at all power levels
NMHC \leq 30ppm (dry volume)	\leq 30ppm at all power levels except 50 kW
Aromatics \leq 1ppm (dry volume)	Average \sim 2ppm; Range: 0.1 to 10ppm


FP1 Test Results: FPS Exit Emissions and H2



FP1 Test Status: Speciated Hydrocarbon Emissions

- In addition to the emissions testing was done to determine the unreacted non methane hydrocarbons (NMHCs) in the FPS exhaust.
- The total amount of NMHCs in the exhaust is very low
- Data is shown for three samples at 50 kW equivalent FPS operation. Data from 50 kW was used since the most species were measurable.



Test Results: NMHC Speciation at FPS Exit (~CSA inlet)



Summary/Future

- Significant progress made from S200 to S400

- Weight
- Volume
- Start time
- FPS Technology
- CSA Technology




- Program ends in FY 04, remaining testing will be completed followed by complete teardown and analysis.

Future Challenges

Gasoline reformer fuel cell power plants




ATR




- 250 L
- 45 min start




Current FPS



- 78 L
- <10 min start



Next generation FPS



Goal

- 35 L
- < 30 sec start

Future Opportunities

FPS Technology Advancement

- Focus on Fuel Processor System (FPS) technology to:
 - Improved catalyst
 - Reduce start time
 - Evaluate membrane separation technology
 - Evaluate PSA technology
 - Reduce weight and volume
 - Improved controllability
- Focus on smaller applications, 5 kW APU size demonstrations and development