

R&D of a PEM Fuel Cell, Hydrogen Reformer, and Vehicle Refueling Facility

Mark F. Wait
Air Products and Chemicals Inc.
Allentown, Pennsylvania, USA

Scott Wilshire
Plug Power, Inc.
Latham, New York, USA

2004 Hydrogen and Fuel Cells Merit Review Meeting
Philadelphia, PA
May 27, 2004

This presentation does not contain any proprietary or confidential information.


Las Vegas Hydrogen Fueling and Energy Station – Compression, Storage and Fueling



Las Vegas Hydrogen Fueling and Energy Station – Distributed Hydrogen Generation and PEM Fuel Cell Power Generation



Nevada Hydrogen Project



City of Las Vegas

© Air Products & Chemicals, Inc., 2004

apci

Program Objectives

- Demonstrate small, on-site H₂ production for fuel cell power generation and H₂ fueling station
- Demonstrate multipurpose vehicle refueling station to dispense H₂/CNG blend and pure H₂
- Demonstrate H₂-fueled stationary 50kW fuel cell
- Evaluate operability/reliability/economic feasibility, and certify integrated power generation and vehicle refueling designs
- Expand the current facility to serve as the first commercial facility when sufficient hydrogen demand develops.

FY03 Budget

- Total Project Budget:
 - \$13,118,282
- Cost Sharing to Date:
 - DOE - \$6,121,049
 - Air Products and Partners - \$6,121,075
- FY2004 Funding
 - DOE - \$360,000

DOE Technical Barriers

DOE HFCIT Multi-Year Plan

- Technology Validation (Section 3.5.4.2), Task #3.
 - B. Storage – Cost, Performance, Structural Integrity
 - C. Hydrogen Refueling Infrastructure – Cost of Hydrogen, Low Availability, Safe Systems
 - D. Maintenance & Training Facilities – Operating and Maintenance Requirements, Personnel Training
 - E. Codes & Standards – Lack of Adopted Codes and Standards
 - I. Hydrogen and Electricity Co-production – Cost and Durability, Permitting, Safety Procedures

DOE Technical Targets

DOE HFCIT Multi-Year Plan

- Table 3.1.2 , Technical Targets
 - Reformer Efficiency, 2003, %(LHV) – 70%
 - Vegas Result, 2000 design – 68% (Current test data)
 - Test data collected while producing < 1 ppm CO purity
 - Vegas has capability to meet target; additional operation to demonstrate capability
 - PSU Program will deliver improvements to 2005 targets
 - Cost of Hydrogen, 2003, \$/kg - \$5.00
 - Vegas Result - < \$5.00
 - Based on evaluation of Las Vegas Energy Station performance using HFCIT MYPP assumptions
 - PSU Program will deliver improvements to 2005 targets

Technical Approach

- **Design, Build, Test**
 - Scaled extension of research
 - Real-world performance and durability testing
 - Site selection, permitting, safety, operability, reliability, maintenance experience clarifies research and development gaps
- **Severe Test Environment – Las Vegas**
 - Desert climate – high summer temps, occasional freezing temps in winter
 - 2000 feet above sea level
 - CO2 Non-attainment (Clark County)



Technical Approach

- **Phase 1**
 - **Define System Requirements**
 - **Finalize System Definition to Requirements**
 - **System Engineering and Design**
- **Phase 2**
 - **Equipment Manufacturing**
 - **Detailed Design for Integrated System Installation**
 - **Installation, Commissioning and Start-up**
- **Phase 3**
 - **Demonstration Operation and Maintenance**
 - **Data Collection and Analysis**
 - **Feedback to Future Designs**
 - **Select Existing System Improvements**

Project Timeline

ID	Task Name	2000				2001				2002				2003				2004							
		Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4		
1	Phase 1 - Engineering and Design																								
2	Phase 2 - Manufacture, Install, Start-up																								
3	Phase 3 - Operation Period																								

- Hydrogen Generator Start-up at Site Achieved August 2002
- Site Opening Dedication in November 2002
- Currently 6 Quarters into the scheduled two year demonstration operating period

Project Safety

- **Safety Evaluated by DOE Safety Panel in Mar 04**

- No major issues, some areas of interest:

- Hydrogen fill rates
 - Underground piping
 - Mechanical joints
 - Pressurized Storage Vessel MIP



- **Site Safety Performance to Date Validates Design**

- No safety incidents for site over 18 months of operation
 - 80+ fuel fills conducted without station incident
 - Inherently safe systems with safety instrumented controls

- **Vegas Energy Station Safety Efforts**

- Hazop, MOC, Quantitative Risk as required
 - Use of applicable industry codes
 - Operational Readiness Inspection (ORI)
 - Trained Operating Personnel
 - Safety Performance Measured

Technical Accomplishments – Hydrogen Generator

● Status Overview

- Over 2800 hours operation
- Satisfactory process operation and product purity capability
- One button start, load following, additional features
- Remote monitoring from Allentown / Sacramento

● Performance

- 68% LHV Efficiency achieved w/ year 2000 design basis equipment , < 1 ppm CO purity control; 70% LHV Efficiency is achievable
- Sound process technology implementation
- Some reliability issues – common component issues
 - Burner failure
 - Spurious thermocouple signals
 - Compressor vibration issues
- Interim inspection of equipment showed equipment in good mechanical condition



Technical Accomplishments – Hydrogen Generator (Cont)

● Operating Experience Information

- Severe diurnal cycling affects ambient conditions, influencing process dynamics
- Seasonal ambient changes influence process dynamics
- Steam system dynamics and control
- More than sufficient instrumentation for safe and reliable control system, but always one or two other data points you could use
- Shutdown / Start-up thermal cycling potential longer term durability issue for catalyst

● Next Operating Test Campaign

- Added primary air flow measurement
- Added steam flow measurement
- Added additional thermocouples along reformer tube to monitor thermal stratification
- 2000 hour on-purpose test run in progress

Technical Accomplishments – Fueling Station (Cont)

- **Status Overview**

- **Approx. 70 H2 / CNG Fills**
- **Approx. 10 H2 Fills**
- **Fleet not yet established**
 - **One H2/CNG LDV (F150 Pick-up)**
 - **One H2/CNG Bus**



- **Performance**

- **Storage systems providing adequate capacity for current demand**
- **Dispenser engineering and design validated (2000 design basis, non-communication fill)**
- **Instrument air has been primary cause of isolated issues**


City of Las Vegas H2 / CNG Bus



Project Overview


- ❖ Completed Fuel Cell system detailed design, fabrication, and testing.
 - Plug Power's first large scale stationary system.
- ❖ Initial startup and qualification testing yielded a number of design changes related to component selection, control and electronic equipment, software algorithms, and gas delivery systems.
- ❖ Executed test program to first qualify individual subsystems followed by final system configuration testing.
- ❖ Test data provided an operational baseline and validation of the interface conditions to support integration into the refueling station.
- ❖ Shipped 50 kW fuel cell system to Las Vegas - October 2001.
- ❖ System commissioned September 2002.

Overview & Equipment



Parameter	Specification
Installation Location	Outdoor
Grid Parallel	Yes
Power Output/Set points (approximate)	15kW, 30 kW, 50 kW
Remote monitoring capability	Via phone line and modem
Electrical Output	480 VAC, 3 Phase, 60 Hz
Power Quality	IEEE 519 or better
Ambient Design Conditions	Minimum Temperature: 10 °F Maximum Temperature: 115 °F
Fuel Supply Purity Operating Supply Pressure Maximum Design Pressure H2 Supply Temperature	Hydrogen 98 % to 99.9 % < 100 ppm hydrocarbons <1 ppm carbon monoxide <1 ppm sulfur 100 +/- 10 psig 150 psig -30°F to 140°F

Overview & Equipment



Key Technical Barriers *

❖ Cost of Electricity (COE)

- Plug Power utilizes a COE approach to assess in order of importance, elements of fuel cell operations on the pathway to commercial viability. The COE model has three elements.
- **Capital or First Cost**
 - O. Stack Material & Manufacturing Costs
- **Operating and Maintenance Cost**
 - E. Durability
 - R. Thermal & Water Management
- **Energy Conversion Efficiency**
 - F. Heat Utilization
 - G. Power Electronics

* as identified in the Multi-Year Research, Development, and Demonstration Plan Section 3.4.4.2 – Barriers

Technical Barriers

❖ Fuel Cell System

- Approach changed from single stack to eight manifolded stacks
- Limited experience in manifolding stacks, cell voltage scanners
- Balance of plant issues included cathode humidification
- Overall control system utilized Lab View - lacked robustness and ability to easily change software as changes were identified
- Limited lifetime of this generation of stack materials (200 hours in 2001 to >8000 hours today)
- Electrical integration and control of stacks required development of new approaches
- Viability of system design deemed not able to be made commercially viable. First cost of \$6000 per kW too high for marketplace

❖ Site Integration

- Initial experience in connecting fuel cell to third-party reformer
- Grid interconnection initially challenging (approvals)

Technical and Program Accomplishments

❖ Fuel Cell System Design


- Cell voltage monitoring critical to reliability
- Ability to leverage existing design (Platform approach)
- System integration experience
- Key learning of electrical noise issues, resolutions
- Manifolding stacks
- Three Phase Inverter integration
- Basic understanding of stack humidification & water management

❖ Site Integration

- Fuel cell system – Reformer integration.
- Hydrogen design requirements


Technical and Program Accomplishments

Las Vegas System Run Summary
8/2/02 - 9/19/03




System Run Time: 1414 hours
Power Produced: 43,500 kWh
System Efficiency: 36.3%
Stack Efficiency: 46.8%

Las Vegas System Voltage at 300 A
8/8/02 - 10/7/02



Impact of humidification change
Cell degradation rate decreased
to 5 μ V, translating to projected
stack life of 12,000 hours.

Adoption (as a function of Technical Barriers)



Scott Wilshire

Director of Marketing Engagement

518-782-7700 X1338

scott_wilshire@plugpower.com

Responses to Prior Year Comments

- **Data Collection, Analysis and Econ Evaluation**
 - Interim evaluations concluded and reports in process
 - Data exchange with collaborating entities underway
 - Additional data collection and evaluation to follow
- **Site Footprint (relatively large footprint)**
 - Energy Station site took advantage of available plot
 - Additional unoccupied foundation is part of site
 - Other Air Products sites are much smaller
 - PSU site will be much smaller
- **Educational Benefits**
 - Significant international and national visitor traffic
 - International Energy Agency
 - DOE Safety Panel
 - Numerous conference tours (PowerGen, APTA, etc.)
 - Permit experiences shared

Future Work

- **Conclude current operating period**
 - **Collect operating data for analysis**
 - **Addl Generator analysis for added data pts**
 - **Addl economic evaluation**
 - **Incorporation of lessons learned into PSU**
 - **H2 Generator Packaging**
 - **H2 Generator Process and Control Improvements**
 - **System Design, Costs and Economics**
 - **Support CLV fleet expansion**
- **Planning for continued DOE support of site beyond current operating period**
 - **Potential for upgrade of fueling systems for 350 Bar / 5000 psig fueling (systems mechanically rated for 5000 psig)**
 - **Potential for upgrade of fueling systems for communication based fill**
 - **Continued use of Vegas asset as a R&D test bed facility**
 - **Support Vegas Fleet Build-out**
 - **Current fleet of 268 CNG vehicles**
 - **Progressive in testing / adopting alternative fuels**

Collaborations

- **Special Thanks to Dr. Venki Raman, Air Products**
- **DOE HQ and Golden Field Office**
- **Dan Hyde, City of Las Vegas Fleet Site Mgr**
- **Plug Power – Rob Dross, Dave Parry, Bob Sinuc, Scott Wilshire**
- **Sandia National Laboratory – Andrew Lutz**
- **International Energy Agency**
- **DOE Safety Panel**

PLUG POWER. PLUG WILL.

Thank you

tell me more
www.airproducts.com